

Anchor solution on pitched roof | top-fix | Roof sealing membranes





Mounting instructions

- Safety instructions 2
- General conditions & Notes on mounting 3
- Tools, system components and optional components 4-5
- Mounting the substructure 6–16
- Mounting optional articles 17
- Maintenance of the mounting system 18



Safety instructions



The following instructions are to be understood as generally valid for our novotegra installation system and are to be applied accordingly, regardless of the particular roof type and installation system.

Systems may only be installed and commissioned by persons who are able to ensure that they are carried out in accordance with the regulations on the basis of their professional qualifications (e.g. training or activity) or experience.

All relevant national and locally applicable occupational health and safety regulations, accident prevention regulations, standards, construction regulations and environmental protection regulations as well as all regulations of the employers' liability insurance associations must be observed.

- During the work, safety clothing must be worn in accordance with the relevant national regulations and guidelines.
- The assembly must be carried out by at least two persons in order to be able to guarantee help in case of an accident.
- The national regulations for work at heights and on roofs must be observed.
- The electrical work must be carried out in compliance with the national and locally applicable standards and guidelines in compliance with the safety regulations for electrical work.

The installer is responsible for dimensioning the novotegra mounting system.

Before installation, it must be checked whether the mounting system meets the static requirements on site For roof systems, the on-site load-bearing capacity of the roof must also be checked. Please note our instructions on static calculations, which can be viewed at novotegra.com/downloads.

The installer is responsible for connecting the interfaces between the mounting system and the building. This also includes the tightness of the building envelope. The mounting system must always be statically calculated individually for each project using the Solar-Planit design software. With the exception of concrete facades, which are calculated by novotegra GmbH.

The mounting system is suitable for mounting PV modules with standard market dimensions.

The installation instructions of the module manufacturers must be observed and complied with.

There is no inspection by novotegra GmbH regarding constructability or mounting guidelines.

The specifications of the cable and inverter manufacturers must be observed. If there are any contradictions to these installation instructions, please be sure to consult your novotegra GmbH sales team or - in the case of components not supplied by novotegra GmbH - the manufacturer concerned before installing the novotegra mounting system.

It must be ensured that a copy of the assembly instructions is within reach in the immediate vicinity of the work on the construction site.

Since our assembly systems are constantly being further developed, assembly procedures or components may change. Therefore, please check the current status of the installation instructions on our website novotgera.com/downloads before installation. The assembly sequence of these instructions must be observed. We will also be happy to send you current versions on request.

In the event of improper use and non-compliance with our safety instructions and installation specifications, as well as non-use of associated installation components or use of third-party components that are not part of the installation system, all claims under guarantee, warranty and liability vis-à-vis novotegra GmbH shall lapse. The user is liable for damage and resulting consequential damage to other components such as PV modules or to the building itself, as well as for personal injury.

The permissible roof pitch for the use of the mounting system in accordance with these installation instructions is 0 to 60 degrees for installation parallel to the roof on a pitched roof and 0 to 5 degrees for elevated installation on a flat roof. Facade systems are to be mounted parallel to the facade.

The grounding / potential equalization of the mounting system must be carried out in accordance with the national and locally applicable standards and guidelines.

If all safety instructions are observed and the system is installed properly, there is a product warranty claim of 12 years. Please note our warranty conditions, which can be viewed at novotegra.com/downloads.

The system can be dismantled in reverse order to the steps described below.



General conditions

Location:	pitch roof
Roof inclination:	0°-60° (Depending on anchor manufacturer)
Roof cover:	Bitumen and roof sealing membranes (EPDM, TPO, FPO, PVC)
Module mounting:	portrait/landscape
Rail length:	max. 8,5 m then expansion joint
Module field size:	40 m, then module field separation (deviating specifications of the anchor manufacturer must be checked)

General installation instructions

The suitability of the mounting system for the respective project must be checked on a case-by-case basis using the existing roof covering and roof structure. The roof covering, roof structure or façade must fulfil the requirements of the mounting system in terms of load-bearing capacity, load-bearing structure and state of preservation.

For roof-parallel installation with the clamping system, two module support rails per module must be mounted symmetrically under the modules for equal load transfer into the substructure. Alternatively, the roof-parallel installation can also be installed with insertion rails. The specified tightening torques must be adhered to and checked randomly on site.

The load-bearing capacity of the roof, the roof structure (rafters, purlins, trapezoidal sheet metal, concrete ceilings, number of adhesive seamed roofs, etc.) or the facade (wall material) must be checked by the user on site or have it checked.

Physical building aspects concerning insulation penetrations (e.g. condensation) must be taken into account by the user.

The contents of these installation instructions describe the installation of the substructure on anchors installed on site. The load-bearing capacity values of the anchors are to be taken from the manufacturer's specifications and entered into the Solar-Planit planning software. The structural design and arrangement of the anchors can be found in the Solar-Planit planning documents.

The individual installation steps for module upstand installation are explained below. Reference is made to installation variants for the various design options. The associated work steps follow.



Tool and equipment



Electric srewdriver



Mitre saw



Torque spanner 20-50 Nm



special nut socket 8 mm



special nut socket 13 mm



special nut socket 18 mm

Mounting system components*



C-rail 47



Rail connector set C



Expansion joint C 47



Middle clamp Set C



End clamp Set C



Module slip guard set M8/ M6



Rail connector set C47 S



locking nut M10 with 18 AF hexagon drive



locking nut M12 with 18 AF hexagon drive



Slip guard/End cap set C47

Mounting system components – optional**



Cable-tie clip for profile flange



Cabel-Clip d = 10 mm



Contact latch module clamp



Grounding connector C-rail



End cap C47 black

^{*}The components vary depending on the requirements of the roof, the structural analysis and the choice of components and may deviate from the images above

^{**}Optionally available installation system components, e.g. for improving the aesthetics of the system, cable management or grounding of the installation system.



Mounting system components – variations***







Rail connector set C 38



C-rail C71



Rail connector set C 71



C-rail C95



Rail connector set C 95



Expansion joint C 38



Expansion joint C 71



Expansion joint C 95



Slip guard/End cap set C 71



Slip guard/End cap set C95


^{***}The components vary depending on the requirements of the roof, the structural analysis and the choice of components and may deviate from the images above



Mounting the substructure

1

Meassuring module field






Determine the position of the anchor.

The position of the anchor must be determined taking the static calculation into account.

Module installation portrait

The optimum clamping point of the module must be determined and marked at the roofing membrane. The module support rails run horizontal. The position of the anchor can be found in the planning documents.



Module installation landscape

The optimum clamping point of the module must be determined and marked at the roofing membrane. The anchor must be placed at the marking. The module support rails run vertikal. The position of the anchor can be found in the planning documents.


no

novo-tip:

The optimum clamping ranges can be found in the module manufacturer's installation instructions.




2 Mounting the anchors according to the manufacturer's instructions





Rail mounting





⚠ Notice:

There is a risk of waterlogging on the roof. If the rail is screwed flush to the roof cover, the water cannot run off. Water drainage can only be guaranteed, if the rail is at an appropriate distance from the roof. This distance must be determined on site and adhered to.




novo-tip:

The height of the rail can be adjusted by the position of the locking nut. To do this, screw the locking nut higher or lower on the thread.










A The C-rail must be placed on the lower locking nut.



B The upper locking nut must be screwed on and screwed flush with the rail base. The upper locking nut must be fully seated in the threaded area of the anchor.

Tightening torque: 50 Nm Depending on anchor manufacturer.



Mounting variations



Rail connection on z-shaped anchor








▲ Notice:

The anchors must be installed on the roof in accordance with the manufacturer's instructions. The number of anchors can be found in the Solar Planit planning documents. The applicable standards and guidelines must be observed.






Warning:

The connection between the rail and the anchor is not included in the supply. The specifications of the anchor manufacturer must be checked.



The C-rail must be attached to the Z-shaped anchor at a 90° angle.
















Warning:

Risk of injury when sawing the rail to size

There is a risk of cutting yourself on the sharp edges of the rail and the saw blade.

- Comply with UVV
- Wear protective gloves
- Wear safety goggles



Connecting the rails.

Push the ends of the rails tightly together, place the rail connectors centrally and screw together. Using the bolts contained in the set.


Tightening torque 50 Nm Max uninterrupted rail length 8,5 m, then expansion joint. Depending on anchor manufacturer.



Mounting of the rail connector C 47 S.

- a Push the rail connector set halfway into one of the rails to be connected and secure it by self-tapping screws each on both sides approx. 20 mm from the rail end.
- (b) Next push the other rail completely onto the rail connector set until both rail ends make contact and screw it tight as described above.

Max uninterrupted rail length 8,5 m, then expansion joint.
Depending on anchor manufacturer.






Installing expansion joints on C-rails







Warning:

Risk of injury when sawing the rail to size

There is a risk of cutting yourself on the sharp edges of the rail and the saw blade.

- Comply with UVV
- Wear protective gloves
- Wear safety goggles



Warning:

A expansion joint must not be installed under a module.



Place rail ends onto the gap, apply the rail connector and connect it to the rail at the fixed and movable sides using the mounting screws. Tighten the screws firmly on the fixed side. The screws on the movable side are coated in red and must be released again after tightening (approx. ½ turn).

Distance of adjacent rail ends C-rail 38 and 47: 20 mm C-rail 71 and 95: 40-50 mm

Tightening torque: 50Nm Max. Rail length 8.50m, then set floating bearing. Separate module field after 40 m. Depending on anchor manufacturer.









Warning:

A expansion joint must not be installed under a module.

B Mounting end clamp by expansion joint.

An end clamp must be placed on each side of a expansion joint.

novo-tip:


It is possible to mount the end clamp flush with the end of the rail.



6 Mounting moduel slip guard








A Module mounting portrait

From a roof pitch > 10° the slip guard device must be fitted to the frame holes of each module in the bottom row of rails.






7 Module mounting Clamping system















Tightening torque Middle clamp 10 Nm.

Tightening torque End clamp 8 Nm.





Space requirement for Middle and End clamps.

The modules must be pushed all the way onto the rail nut of the Middle and End clamps.

Tightening torque Middle clamp 10 Nm.


Tightening torque End clamp 8 Nm.

d novo-tip:

The End clamp can also be installed aligned with the rail end.

If End caps are fitted, the C-rail must be cut to length 1 cm longer than specified in the rail sawing plan.








Mounting optional articles

1 Installing contact latch



Warning:

The applicable standards and guidelines, e.g. lightning protection standard, must be observed.


Assembly of contact latch for middle clamp.

Push the contact latch on the sliding plate over the vertical webs of the middle clamp up to the screw.

2 Mounting grounding connector







Warning:

The applicable standards and guidelines, e.g. lightning protection standard, must be observed.

Install grounding connector set.

One grounding connector must be installed per module field.

Earthing wire: 20 Nm Earthing cable: 10 Nm



Maintance mounting system

The mounting system must be checked for stability and function at regular intervals during plant maintenance. We recommend an annual visual inspection.

In addition to the visual inspection of the components, we recommend a random check of the connections and the safe and correct position of the ballasting on the base rails and ballast trays. The screw connections should also be checked and, if necessary, retightened in accordance with the tightening torques specified in the assembly instructions.

All system components should be checked for damage caused by, for example, weathering, animals, dirt, deposits, adhesions, fouling (especially on green roofs), roof penetration, sealing, stability and corrosion. The inspection of the system and maintenance work must be carried out by a specialist company that has experience with electrical systems and work with mounting systems, or by an expert. After unusually strong impacts (e.g. from earthquakes, heavy snowfall, storm events, etc.), an inspection of the system must always be carried out.

novotegra GmbH

Eisenbahnstraße 150 | 72072 Tübingen | Germany Tel. +49 7071 98987-0, info@novotegra.com www.novotegra.com

> Errors and omissions excepted. Status: 06/2025